



WOLF TRAIL™
ENGINEERING
NC P-1817 | SC 5872

March 26, 2026

Mr. Patrick Jones
Planning, Design, and Construction
UNC Charlotte
9151 Cameron Boulevard
Charlotte, NC 28223

Re: Addendum #2 – UNC Charlotte – Kenndy Hall Roof Replacement
SCO ID # 25-30579-01A

This addendum shall become part of the bidding package for Kenndy Hall Roof Replacement
SCO ID# 25-30579-01A

1. Are we required to open a service agreement with Piedmont Natural Gas agreement for this project? What is the purpose of it if so?
 1. Piedmont Natural Gas stops at the meter, there is no need to open a service agreement. Any work on the natural gas shall be performed by a licensed mechanical contractor.
2. Who is the “MFG” for the page R-2 Detail #1 – “Pre-Manufactured Pre-Finished Fascia Cover?”
 1. There is a section in the specifications (SECTION 07 62 00, SHEET METAL FLASHING & TRIM) for pre finished metal. The manufacturer is chosen by the contractor.
3. Will the outside corners of the new Fascia metal be welded?
 1. The fascia shall have lapped joints. The outside corners shall be soldered and painted to match the fascia metal.
4. Solder: Shall be “Lead Free”.

Sincerely

Douglas Buchanan, PE
President | Wolf Trail Engineering
doug@wolftrailengineering.com | 704-533-2327